

## Sample Drawing Notes

Install INCUE ICRA Automation System for continuous indoor air quality monitoring. This includes physical installation of INCUE ICRA Automation Air Quality Sensor(s), Differential Pressure Sensor(s), Temperature and Humidity Sensor(s), and IoT Gateway; it also includes digital registration/installation of the INCUE App. Desktop, Laptop, Tablet, and Phone formats are supported through a Web Browser, Android, or iOS.

Contractor shall complete Planning Checklist, Installation Checklist, and Sign Off within the App. Contractor shall complete Daily Tasks, including pictures as necessary, within the app. Contractor Shall correct any notifications alerted by INCUE Sensors/App within the timeframe specified by Infection Control Risk Assessment and document occurrence and correction methods within the App. Contractor shall generate a Monthly Compliance Report saving within App Documentation as well as presenting a copy to Facility Management each month during Construction. The contractor shall generate a closeout report at the close of construction, save it within App Documentation, and present a copy to Facility Management. For more information, visit <https://incue.app/support>.